



PROJECT DESCRIPTION REPORT





Table of Contents

			Page
1.	Intro	oduction	1
2.	The l	Proponent	2
3.	Proje	ect Location	3
4.	Auth	norizations Required	8
5.	Proie	ect Information	9
	5.1	Nameplate Capacity and Classification	
	5.2	Land Ownership	
	5.3	Energy Sources	
	5.4	Project Components	
		5.4.1 Solar Modules and Mounting System	
		5.4.2 Inverters, Transformers and Electrical Collection System	
		5.4.3 Access Roads	
		5.4.4 Perimeter Fence and Communications Tower and Lighting	11
		5.4.5 Temporary Construction Area and Permanent Parking	11
		5.4.6 Water Crossings	
	5.5	Project Activities	12
		5.5.1 Construction	12
		5.5.2 Operation and Maintenance	16
		5.5.3 Decommissioning	18
6.	Poter	ntial Environmental Effects	21
	6.1	Cultural Heritage and Archaeological Resources	21
	6.2	Natural Heritage Resources	21
	6.3	Water Bodies	24
	6.4	Air, Odour and Dust	
	6.5	Noise	
	6.6	Land Use and Resources	
	6.7	Provincial and Local Infrastructure	26
	6.8	Public Health and Safety	
	6.9	Areas Protected under Provincial Plans and Policies	27
7.	Bene	efits of the Project	27





List of Figures

Figure 1:	General Location of GoldLight in Ontario	4
Figure 2:	Project Location and Context	5
Figure 3:	Project Location, Natural Features and Land Uses	6
Figure 4:	Conceptual Component Layout	7
	List of Tables	
Table 1:	Expected Authorizations for the Project	8
Table 2:	Construction Activities	12
Table 3:	Operations and Maintenance Activities	16





1. Introduction

Canadian Solar Solutions Inc., acting on behalf of GoldLight LP, proposes to develop a solar facility with a maximum name plate capacity of approximately 10 megawatts (MW) alternating current (AC), located near Pefferlaw, in the Town of Georgina and the Region of York, Ontario. The renewable energy facility will be known as GoldLight and will be rated as a Class 3 Solar Facility. GoldLight LP has received a contract from the Ontario Power Authority (OPA) for the sale of electricity generated by this renewable facility through the province's Feed-in-Tariff (FIT) program (enabled by the *Green Energy and Green Economy Act*, 2009). The project will require a Renewable Energy Approval (REA) as per *Ontario Regulation 359/09* under Part V.0.1 of the Ontario Environmental Protection Act.

This *Project Description Report (PDR)* is being submitted to the Ontario Ministry of the Environment (MOE) as required under the Renewable Energy Approvals (REA) process as outlined in *Ontario Regulation 359/09*, and was made available for public review and comment prior to this final submission to the MOE. Other draft repots made available for public review prior to this submission included:

- Design and Operations Report;
- Construction Plan Report;
- Decommissioning Plan Report;
- Noise Study Report;
- Natural Heritage Assessment (4 reports);
- Water Assessment;
- Archaeological Assessments;
- Cultural Heritage Screening; and,
- Cultural Heritage Assessment.

These documents will be posted on the project website (<u>www.goldlightsolar.com</u>).

The PDR provides an overview of the proposed project including location, components, activities and potential negative environmental effects and summarizes the content of the above-listed reports.





2. The Proponent

Canadian Solar Solutions Inc. is managing and coordinating the approvals process for GoldLight LP. Canadian Solar is an experienced developer, owner and operator of power generation and energy delivery assets. Company activities include developing, building, owning and operating renewable energy facilities. Canadian Solar strives to satisfy various environmental approval requirements and obtain regulatory approvals that vary depending on the jurisdiction, project capacity and site location. In addition, GoldLight LP and Canadian Solar Solutions Inc. are building long-term relationships with the communities that host their projects and are committed to the health and welfare of the Town of Georgina and the Region of York, Ontario.

Contact information for the proponent is as follows:

Full Name of Company: GoldLight LP

Prime Contact: *Mark Feenstra*

Address: 545 Speedvale Ave. W., Guelph, Ontario, N1K 1E6

Telephone: 519-837-1881 x2342

Fax: 519-837-2550

Email: <u>Mark.Feenstra@na.canadiansolar.com</u>

Dillon Consulting Limited (Dillon) is the consultant responsible for the preparation of REA-related reports for GoldLight. The contact at Dillon is:

Full Name of Company: Dillon Consulting Limited

Prime Contact: Katharine Myrans, REA Project Coordinator

Address: 235 Yorkland Boulevard, Suite 800, Toronto, Ontario, M2J 4Y8

Telephone: (416) 229-4647 ext 2381

Fax: (416) 229-4692

Email: <u>kmyrans@dillon.ca</u>





3. Project Location

The proposed Class 3 Solar Facility is located at 7130 Old Homestead Road, approximately 8 kilometres from the community of Pefferlaw. **Figure 1** shows the general location of the project in Ontario. The project location covers part of Lots 8 and 9, Concession 5, in the Town of Georgina and consists of 38.17 hectares of privately owned land (leased by the proponent) with geographic coordinates (centroids) as follows:

Latitude: 44° 17' 26.06" N

■ Longitude: 79° 17' 47.95" W

"Project location" is defined in Ontario Regulation 359/09 to be "a part of land and all or part of any building or structure in, on or over which a person is engaging in or proposes to engage in the project". Figure 2 has been provided for geographic context. Figure 3 shows the project location as the outer boundary within which all project components will be located. Figure 3 also identifies natural features and water bodies (based on the records review and site investigation) at and within 300 metres of the project location. Figure 4 provides detail on the location of facility components. Additional site plans are provided in the Design and Operations Report.








Figure 1: General Location of GoldLight in Ontario







GoldLight Figure 2: Project Location and Context

Legend

Local Road


Project Location

120 m Project Location Setback 120 m Project Location Setback
300 m Project Location Setback

Lots/Concessions


Image Provided by Google Earth Pro, 2011


Produced by Dillon Consulting Limited under License with the Ontario Ministry of Natural Resources © Queen's Printer for Ontario, 2010





Created By: GSM Checked By: JLP Date Created: 032712 Date Modified: 062712 Project Centroid: 44.290574, -79.296655 File Path: I:\GIS\114649 - GoldLight\ Mapping\PDR\Figure 2
GoldLight Project Location PDR.mxd







4. Authorizations Required

Table 1 provides a list of authorizations (applicable permits, agreements, licenses, approvals and confirmation letters) that GoldLight LP expects may be required in addition to the Renewable Energy Approval. These will be obtained prior to construction of the proposed solar facility, if required. It is not anticipated that the project will require a federal environmental assessment.

Table 1: Expected Authorizations for the Project

Authority, Agency or Governing Body	Requirement (if needed)
Electrical Safety Authority	 Safety Inspection and Electricity Safety Code Certification (if needed)
Hydro One Networks Inc.	 Customer Impact Assessment – Integration of the project within Hydro One and effects on customers (if needed) Construction Cost Recovery Agreement (if needed)
Lake Simcoe Region Conservation Authority (LSRCA)	Regulated Area Permit for development in natural hazard lands under consultation with LSRCA (if needed)
Landowner	Lease Agreement
Ontario Energy Board	License to generate electricity
Ontario Ministry of Natural Resources	Permitting under Endangered Species Act (if needed)
Ontario Power Authority	■ FIT contract
Town of Georgina and/or Region of York	 Building Permit(s) (if needed) Road User Agreement (if needed) Drainage Assessment (if needed) Entrance and signage permits (if needed)





5. Project Information

5.1 Nameplate Capacity and Classification

GoldLight is designed to generate a maximum of 10 MW AC of electricity. According to Part II, Section 4 of *Ontario Regulation 359/09*, the proposed project is a Class 3 Solar Facility. The characteristics of a Class 3 Solar Facility, as described in the regulation, are as follows:

- the location of solar photovoltaic (PV) collector panels and devices are at any location other than mounted on the roof or wall of a building; and,
- the name plate capacity of the solar facility is greater than 12 kilowatts.

5.2 Land Ownership

The land is privately owned and will be leased to the proponent, GoldLight LP. The legal description for the property is: Part Lot 8, Concession 5, Georgina, Part W1/2 Lot 9, Concession 5, Georgina as in R215103, Town of Georgina, Region of York.

5.3 Energy Sources

The primary source of energy that will be used to generate electricity will be the kinetic solar energy of moving photons, which will be converted to electrons by the solar PV cells. This will create direct current (DC) electricity which will be inverted to AC at the project location.

5.4 Project Components

PV panels will be the technology used to convert solar energy into electricity. With exposure to sunlight, the solar modules convert solar radiation into direct current (DC) electricity through a PV process. The PV process occurs when the energy from the sunlight is transferred to semiconductors contained in the modules. DC electricity generated from the panels will be collected and converted into AC electricity by inverters. From the inverters, the electricity will be sent to the step-up substation transformer where it will be metered and sent to the local distribution system.

Details about the project components, both temporary and permanent, that make up the solar energy facility are provided below.





5.4.1 Solar Modules and Mounting System

Approximately 30,000 - 100,000 PV panels of between 60 - 300 watts each will be installed for GoldLight. It is anticipated that the following panels, or similar, will be used: Trina TSM-DA05 220W or Canadian Solar CSA 230W PV solar panels. The modules are designed for outdoor use. The panels will be aligned in rows facing due south (approximately 4 - 10 metres apart) and will be mounted on fixed racking systems which will be attached to galvanized steel and/or aluminum support structures. Based on the results of continued geotechnical assessment during engineering and construction, driven piles, screw piles or concrete foundations will be used as appropriate to minimize potential negative environmental effects.

5.4.2 Inverters, Transformers and Electrical Collection System

DC electricity generated from the panels will be transmitted through underground wires connected to combiner boxes where a number of incoming wires from the racks will be combined into a single outgoing cable. From the combiner box, the DC current will be transmitted below ground to one of ten inverter stations. Each inverter station will consist of two inverters (to convert the DC electricity into AC electricity suitable for distribution to the local grid) and an inverter transformer. The inverters will be SMA's Sunny Central and will be rated for 500 kVA of continuous output power. Each inverter will have its own cabinet-type enclosure and will be mounted on a concrete platform.

The inverter transformers located at the inverter stations will be Siemens 13800 V with a power rating of 1000 kVA. The inverter transformers will be located next to the inverters on a concrete platform and will boost the AC voltage which will then be distributed below ground (requires trenching) to a main transformer located within the substation. The step-up transformer is expected to be an 11.5 MVA pad mount transformer (make/model to be determined) and will increase the voltage further for connection to the Hydro One transmission grid. A short overhead line mounted on poles will be constructed to the point of common coupling (at the end of the main access road and Old Homestead Road municipal right-of-way). Appropriate grounding systems will be installed for the project, where necessary.

The substation will be a double-walled transformer or have secondary containment.





5.4.3 Access Roads

A main access road will be needed for the construction equipment and related vehicles to enter the project location off Old Homestead Road. Internal access roads will also be developed for construction purposes and to provide long-term access for maintenance during operation. The roads will be 3.7 - 5 metres wide and will be granular. Geotextile fabric may be used where necessary to improve structural integrity and preserve the granular. If necessary, culverts will be installed beneath the access roads at locations where conveyance of surface water drainage is required.

5.4.4 Perimeter Fence and Communications Tower and Lighting

For the safety of the public and to prevent vandalism, a perimeter fence will be installed. This will be a chain link fence as required by the Electrical Safety Authority (approximately 2.7 metres in height) around the perimeter of the project location with locked gated entrance(s) and 3-strand barbed wire at the top. For security and maintenance purposes, lights may be installed near the entrance of the facility, and task-specific lights will be provided as necessary. These will be appropriately shielded or directed and may also be motion-sensored to address potential negative effects, as necessary. A communications tower will be installed and operated by Hydro One, for emergency disconnect purposes only.

5.4.5 Temporary Construction Area and Permanent Parking

During construction it will be necessary to designate/construct a temporary storage/laydown and construction staging area for the construction office trailers, portable washrooms, first aid stations, vehicle parking, construction equipment parking, storage sheds, truck unloading/loading, waste disposal pick-up areas, and equipment and material lay-down. All temporary facilities will be removed when the construction period is finished; however, a portion of the construction laydown area may be maintained after construction for maintenance vehicle parking and other uses, as required.

5.4.6 Water Crossings

As shown in **Figure 3**, water bodies have been mapped in relation to the project location. Based on the project layout, no water crossings are anticipated for this project. Water bodies are discussed in further detail in **Section 6.3** of this report.





5.5 Project Activities

The following subsections outline project activities during the construction, operations and decommissioning phases. GoldLight will not require the collection, transmission, treatment, storage, handling, processing or disposal of sewage, biogas, biomass, source-separated organics or surface water. The facility will not discharge contaminants to the air. The facility will be designed and constructed so as to minimize potential negative impacts to stormwater runoff and drainage.

5.5.1 Construction

The following activities associated with construction of the solar facility are anticipated to take between 6 - 9 months and are scheduled to begin spring/summer 2013. They will occur in the relative order in which they are presented in **Table 2**. More information, including construction schedules, materials and equipment, is available in the *Construction Plan Report*.

Table 2: Construction Activities

Activity	Description
Survey and staking of the project location	At the beginning of the construction phase, the site will be surveyed and staked to delineate the boundaries for fencing, access roads, excavations and foundation locations. The survey will identify the location of underground utilities and/or infrastructure. Any significant or provincially significant environmental features and their applicable setbacks (e.g., water bodies, significant wildlife habitat, etc.) will also be clearly demarcated. Areas to be avoided may be fenced and/or flagged, as appropriate.





Activity	Description
Clearing, ground levelling, compacting and grading	Graders, bulldozers, scrapers, soil compactors, dump trucks, and wheel loaders will be used to prepare the site. Clearing of some trees and vegetation may be required for the installation of panels and racking. Larger tree cutting will be conducted using chainsaws, and stumps, roots and brush vegetation will be removed using excavators and small bulldozers. Permits for tree removal will be obtained if required by the Town of Georgina or the Region of York.
	Major excavation works or fill placement are not expected for the project. The primary excavation work is likely to be limited to soil removal for various foundations, access roads and digging trenches to run underground electrical cables. Excavation may also be required for the installation of the communications tower.
Drainage and erosion control	Specific details regarding surface drainage and any construction requirements will be established as part of a stormwater management plan which will be prepared prior to construction and during the detailed design phase of the project. The measures will remain installed throughout the construction period and will be routinely inspected by the contractor.
Installation of perimeter fences and security lighting	Permanent fencing will be installed along the perimeter of the project location. The fence will be approximately 2.7 metres in height with 3-strand barbed wire at the top (or as required by the Electrical Safety Authority (ESA)). A gated entrance will be installed either at the site entrance at Old Homestead Road or where the internal access road intersects the temporary construction laydown area.
	For security and maintenance purposes, lights may be installed near the entrance of the facility and task-specific lights will be provided as necessary. They may be motion-sensored and/or shielded or directed to address potential negative effects, as necessary.





Activity	Description
Construction of access roads and installation of temporary power	During construction of the access roads, the topsoil will be stripped and stored. Some cut and fill may be required; however, it is expected that the subgrade material will be comprised of existing native granular deposits. The depth of the roadbed will be constructed as required to transport loads associated with construction and maintenance of the project. Geo-grid and geotextile fabric may be used, where necessary, to improve the structural integrity of the road base and to preserve the granular. Where necessary, culverts may be installed beneath the access roads to provide greater stability.
	During the construction period, on-site electricity to power equipment will be obtained from temporary generators supplied by the contractor. Electricity required for temporary construction offices, lighting and other purposes will be arranged for and obtained from the local electricity provider.
Delineation of temporary storage and construction areas and installation of temporary facilities	After site grading (discussed above) a layer of granular material will be installed to provide an adequate base for construction vehicles, equipment and material laydown. This area may be decommissioned and all temporary facilities removed when the construction period is finished. This area (or a portion of it) may remain as a permanent component after construction for maintenance vehicle parking and other similar uses.
Construction of foundations	 The substation area and ten inverter station areas will be prepared/excavated as needed and foundations for the equipment installed. Foundation types may consist of the following: concrete pre-cast pads which are transported to the site by truck and subsequently set into position by a crane; concrete cast-in place pads, constructed on-site by pouring ready-mix concrete into forms; or ground screws or plate-mounted steel beams.





Activity	Description
Installation of supports, racking and PV modules	An aluminum or steel racking system will be installed on the foundations to support the panels. Foundation types may consist of ground screws or plate-mounted steel beams, which will be installed using a mechanical hydraulic or vibratory pile hammer mounted on a rig to screw or drive the piles into the ground. PV panels will then be mounted on the racks. During the construction phase, the installation of solar panel piles and underground cables may require dewatering if groundwater starts to collect in the trenches and holes dug for these project components. Any water taking would only involve small quantities (<50,000L/day) and will be restricted to low flow time periods.
Installation of wiring and inverters/transformers	Inverters, inverter transformers and the substation transformer will be placed on foundations by a crane. Prior to their installation, trenching will occur using a backhoe (or similar equipment) for the placement of underground cabling. The trenches will be approximately 1 metre deep by 0.5 metres wide and will be backfilled to grade. Overhead cabling supported by poles will be installed within the
	project location to connect the substation to the point of common coupling, located at the site entrance on Old Homestead Road.
Clean-up of work areas	After all major construction activities are completed work areas will be returned to their pre-construction condition or similar. All construction-related waste and excess materials brought to the site will be removed by truck and reused, recycled, or disposed of as applicable by a licensed contractor in accordance with provincial guidelines.
Site landscaping	Site restoration and reclamation is planned for as much of the project location as possible, including along access roads. The restoration and reclamation strategy may include re-contouring of the land to complement natural drainage patterns (in accordance with a stormwater management plan), management and replacement of subsoil (if applicable) and/or topsoil followed by re-vegetation.

All construction activities will be conducted by licensed contractors in accordance with required standards and codes and all activities will abide by local laws and requirements. All construction-related activities will be conducted within the project location outlined in **Figure 3**. Testing and commissioning of the facility will occur over the last few weeks of construction. During





construction, no hazardous materials, including fuel, oils or grease will be stored on-site, although equipment will require their use.

In general, the raw materials for construction will include standard building materials such as concrete, wood, aggregate, and metal. To the extent possible, these materials will be procured from local and/or regional sources where they are available in sufficient quality and quantity, and at competitive prices. Beyond the materials required for construction of the facility, resource requirements for ongoing operation of the project include sunlight and the land-base required for the project location, and any associated electrical lines. For more detail on the materials and equipment that will be used during the construction phase, please refer to the daft *Construction Plan Report*.

5.5.2 Operation and Maintenance

GoldLight will operate year round and generate electricity during daylight hours only. The facility will be continuously monitored and managed remotely using an online system that will track performance in real time and identify any problems that may occur. The communications tower will be used for emergency disconnect only.

Given the topography and location of GoldLight, it is not anticipated that significant ongoing stormwater management activities will be required during operation of the facility. GoldLight LP commits to maintaining the existing off-site drainage patterns and conditions off-site and to further mitigating any impacts to the existing site drainage that the proposed solar facility will cause.

The activities in **Table 3** are associated with the operation and maintenance of the solar facility. These activities will take place over the lifetime of the facility. More information is available in the *Design and Operations Report*.

Table 3: Operations and Maintenance Activities

Activity	Description
Monitoring and meter calibrations	The facility will be monitored remotely twenty-four hours a day off- site to ensure proper power output and to alert the operations staff to potential issues. Most issues can be remotely diagnosed so that the correct individual(s) can be dispatched to the facility to correct any problems.
Routine periodic maintenance and inspection of project components	Site visits will occur as scheduled to visually inspect the solar facility and project location and ensure that the facility is in proper working order. Activities that will occur during these visits may include data





Activity	Description
	collection, regular maintenance (as described below) and any necessary minor repairs such as replacement of weathered electrical components. Security visits may also occur periodically. Transformers, inverters, panels and arrays will be visually inspected during scheduled visits.
Lighting	For security and maintenance purposes, task-specific lighting may be installed. No lights are currently planned around the project perimeter. All exterior lights may be motion-sensored and/or shielded or directed, where necessary, to minimize their impact and will be inspected for burned/broken bulbs. Regularly scheduled maintenance will occur.
Cleaning of panels	Cleaning of panels and equipment will take place as required. No water-taking will occur. All water required for panel washing will be trucked to the project location. No harmful cleaning solutions of any type will be used to wash the panels. Manual snow clearing may periodically be required.
Periodic landscape maintenance	Short native vegetation may be planted once construction activities are complete. It will be necessary to maintain the land in such a way that vegetation does not shade or in other ways impact the solar panels. Regular scheduled maintenance will also occur to manage weed growth. This will be done in consideration of any seasonal limitations outlined in the <i>Natural Heritage Assessment</i> . It is not anticipated that herbicides will be used to manage vegetation.
Major maintenance	Unforeseen, large repairs are not anticipated. Should major maintenance be required it will be performed using existing roads and site access.
Third party inspections and testing	Activities will be carried out as required by the local utility and other governing bodies in addition to any regularly scheduled inspections and testing.
Traffic	No major deliveries are anticipated for maintenance. Minimal vehicle traffic is associated with regular maintenance.
Drainage and erosion control	Stormwater runoff at the project location will be managed as per a stormwater management plan to be developed by the appropriate contractor; and this will be done with consideration to maintaining pre-construction drainage patterns and any recommendations or limitations outlined in the <i>Natural Heritage Assessment</i> or Water Reports. Any implemented measures will be inspected during routine maintenance.





Activity	Description
Waste	The operation of the system does not produce waste of any kind. All debris as a result of maintenance or cleaning will be removed from the site immediately by the contractor.

The project will be scheduled for maintenance as required. Typically, maintenance includes checking the structures and connections. Additional maintenance or service may be required if there are issues such as equipment damage or malfunction; however, this is not anticipated to be a common occurrence. Site inspections for all project components will occur on a scheduled basis. Security and minor maintenance are the only regular activities anticipated on-site.

During the operations phase, no hazardous materials will be stored on-site with the exception of oil for transformers, which will be adequately contained and accompanied by a *Spills Response Plan*.

5.5.3 Decommissioning

Decommissioning consists of the removal of above-ground and below-ground facility components, management of excess wastes and materials and the restoration of project location lands and waters, as applicable. Activities are expected to take between 6 - 9 months. Based on the zoning By-law and current land use it is assumed that the probable future use of the project location after decommissioning will be agricultural. This will be confirmed six months prior to decommissioning to ensure that restoring the land for agricultural purposes remains the most appropriate action.

Properly maintained PV panels have an expected lifespan of approximately thirty to fifty years, or more with equipment replacement and repowering. However, it is assumed that the decommissioning process will begin at the end of the power purchase agreement with the OPA (20 years).

The following activities are associated with the decommissioning of the solar facility and will occur in the relative order in which they are presented below:

- disconnection of facility from the utility power grid;
- disconnection of all electrical equipment at the facility;
- dismantling and removal of PV modules, racking and support structures;
- removal of all above-ground electrical lines and poles;





- dismantling and removal of electrical and electronic devices including inverters and transformers;
- dismantling and removal of communication tower, lighting fixtures and their protective shelters;
- removal of underground wiring, as necessary;
- removal of foundations and any other structures;
- removal of access roads (aggregate and geotextile materials) as necessary;
- removal of all non-native materials, including soil, stone, concrete and asphalt;
- site grading and rehabilitation, as necessary;
- re-seeding, as necessary;
- removal of all waste from the project location; and,
- removal of perimeter fence.

Most of the materials used in a solar facility are reusable or recyclable and some equipment may have manufacturer take-back and recycling requirements.

Any remaining materials will be removed and disposed of off-site at an appropriate facility. GoldLight LP will establish policies and procedures to maximize recycling and reuse and will work with manufacturers, local subcontractors and waste firms to segregate material to be disposed of, recycled and/or reused. It is not anticipated that any waste materials will be left on-site with the possible exception of some access roads (at the landowners' request). The final decision on waste disposal or recycling will be made by the on-site contractor who will refer to the standards of the day for waste generated at the facility.

Through the decommissioning phase, the project location could be restored to its pre-construction condition, or a similar state, the site would be restored by grading to restore terrain profiles and the use of a sub-soiler (if necessary) to relieve compaction and restore the soil conditions for agricultural activities. Rehabilitated lands may be seeded with a low-growing species such as clover to help stabilize soil conditions, enhance soil structure and increase soil fertility. Within the project location there are no water bodies as defined by *Ontario Regulation 359/09*. The operation of the solar facility does not release emissions which could pollute the air and water. Thus, decommissioning activities would not include the restoration of any water bodies.





The site will be restored so that the post decommissioning drainage patterns and quality/quantity of stormwater will be similar to pre-construction conditions. It is not expected that the lands surrounding the facility will require any special remediation. More information is available in the *Decommissioning Plan Report*.





6. Potential Environmental Effects

The following subsections provide a summary of potential effects that may result from the construction, installation, operation, maintenance and decommissioning of the renewable energy facility at the project location and within 300 metres. Mitigation and/or monitoring measures to address potential negative environmental effects to natural features, water bodies, cultural heritage and archaeological features, provincial and local infrastructure, land use, public health and safety and land use plan areas are also described below. Further detail on mitigation measures and monitoring is available in the *Natural Heritage Assessment* and Appendix D of the *Design and Operations Report*.

6.1 Cultural Heritage and Archaeological Resources

The Stage 1 and Stage 2 Archaeological Assessments identified two archaeological sites of value or interest on the property, one within the project location and one within 120 meters of the project location. Both are subject to a Stage 3 Archaeological Assessment prior to any development of the property (see the Stage 1 and Stage 2 Archaeological Assessments). Clearance from MTC on the Archaeological Assessments was received on June 19, 2012.

Based on the results of the *Cultural Heritage Self Assessment*, the project location does not fall within or adjacent to a protected property and no identified cultural heritage resources fall within the project location and no negative impacts are anticipated. However, the self assessment identified potential built heritage features abutting the project location and a full *Cultural Heritage Assessment* was conducted along with a Visual Assessment. These assessments determined that there will be no direct impacts to the cultural heritage features and minimal indirect impact.

Should a previously undocumented archaeological resource or cultural heritage feature be discovered during construction, additional field work, in accordance with Section 48 (1) of the *Ontario Heritage Act*, (1990) will be completed before development can continue. Clearance was from MTC on the *Cultural Heritage Assessment* was received on May 4, 2012.

6.2 Natural Heritage Resources

GoldLight LP has undertaken a Natural Heritage Assessment consisting of a Records Review, Site Investigation, Evaluation of Significance and Environmental Impact Study (EIS). The Natural Heritage Assessment identified the following natural features within 120 metres of the project location:

- Vachell Provincially Significant Wetland Complex;
- 1 unevaluated southern wetland;





- 1 woodland area; and,
- Candidate wildlife habitat including:
 - o Raptor winter feeding and roosting area;
 - o Amphibian breeding habitat;
 - o Turtle Over-wintering Areas;
 - Habitat for Species of Conservation Concern: Western Chorus Frog, Short-eared Owl, Rough-legged Hawk, and Snapping Turtle; and,
 - o Generalized Candidate Significant Wildlife Habitat within 120 metres.

After these natural features were evaluated for significance using procedures and criteria approved by the Ministry of Natural Resources (MNR), the following determinations were made:

- The unevaluated southern wetland was assumed to be provincially significant using the MNR's Rapid Assessment to determine wetland characteristics and ecological functions.
- The one unit of woodland was determined to be significant based on size (298.39 ha), amount of interior habitat (54.81 ha) and its location adjacent to other significant natural features.
- The raptor winter feeding and roosting area was evaluated as not significant. Field surveys, supported by data reported through the Christmas Bird Count (CBC), indicated there are no concentrations of raptors consistently utilizing the area. This determination of not significant also extends to Habitat for Rough-legged Hawks and Short-eared Owls.
- The amphibian breeding habitat was evaluated to be not significant due to lack of species abundance or diversity
- One area was identified as candidate turtle over-wintering area during site investigation work. This mix of open water and field habitat will be treated as significant for turtles until appropriate studies are conducted in consultation with the MNR. Habitat for Snapping Turtles (a Species of Conservation Concern) will be considered during the planned studies.
- Various other forms of wildlife habitat have the potential to occur within 120 metres of the project location. These wildlife habitats have been grouped together and mapped as Generalized Candidate Significant Wildlife Habitat based on guidance from the MNR. The MNR has determined that the wildlife habitat that has been included in this group will not be impacted by the development and operation of a solar farm.





Figure 3 shows natural heritage features within and adjacent to the project location based on the NHA *Evaluation of Significance* work.

Based on the natural environment information collected, the project location was refined to avoid impacts to significant and/or sensitive natural heritage features. The layout of the solar project (as shown in **Figure 4**) has been developed to minimize its footprint and prioritize the protection of natural features.

The potential negative environmental effects GoldLight may have on significant natural features include:

- Removal of 1.36 ha of irregularly-shaped woodland area from Woodland A;
- Damage to revised woodland edge species through soil compaction and trenching where tree roots may occur;
- Alteration of surface water flows to adjacent lands (quantity, quality, infiltrations, conveyance patterns and seasonality of water flow);
- Avoidance of area by wildlife species;
- Soil mobilization resulting in sedimentation of adjacent habitat; and,
- Disturbance/incidental mortality to wildlife species from project activities.

In consideration of these potential environmental effects, mitigation measures have been proposed to minimize or eliminate these effects and maintain the ecological integrity and functionality of these significant natural features. Mitigation and/or monitoring measures proposed include:

- Erosion and sediment control measures prior to site clearing and regularly maintained until the project is operational and vegetative ground cover is re-established;
- Limit vegetation clearing outside of the core breeding period (May 1 July 15) to avoid disturbance to breeding birds; if any vegetation clearing must occur during this period a qualified biologist will conduct nest searches prior to clearing;
- Limit the use of heavy machinery within 5 metres of the dripline of the woodland to prevent soil compaction;
- Implement dust suppression measures as necessary during construction;
- Check engines and machinery for reptiles prior to use; and,





Development and implementation of a grading and water flow management plan which maintains pre-construction surface water flows to adjacent lands (quantity, quality, infiltrations, conveyance patterns and seasonality of water flow).

No residual effects are anticipated after mitigation measures are implemented. The *Natural Heritage Assessment* for this project has been confirmed as complete by the Ministry of Natural Resources on July 4, 2012.

6.3 Water Bodies

GoldLight LP has undertaken a *Water Assessment* to identify all water bodies within the project location and lands within 120 metres. As outlined in the *Water Assessment Report*, within the project location there are no water bodies as defined by *Ontario Regulation 359/09*. A site investigation within the project location confirmed this.

During the records review for water bodies, no records or mapping was provided by any agency to suggest water bodies occurred within the project location or the surrounding 120 metres. After a thorough site investigation was undertaken of the project location and adjacent lands, the determination made during the records review were confirmed.

One small farm pond was observed within 120 metres of the project location. This pond is not hydrologically connected to any other water bodies and is considered to be an artificial body of water. It does not meet the definition of a water body under *Ontario Regulation 359/09*. Therefore, within the project location and surrounding 120 metres there are no water bodies (i.e., permanent watercourses, intermittent watercourses, seepage areas or lakes), as defined by *Ontario Regulation 359/09*. Based on this, water crossings will not be required for this project. Further, a *Water Body Report*, as outlined in Sections 39 and 40 of *Ontario Regulation 359/09*, is not required.

The potential negative environmental effects GoldLight may have on water bodies within 300 metres include:

 Vegetation clearing and grading may increase surface runoff and soil mobilization may impact receiving water bodies.

In consideration of these potential environmental effects, mitigation measures have been proposed to minimize and/or eliminate these effects and maintain the ecological integrity and functionality of applicable water bodies identified within 300 metres of the project location. These mitigation measures will also mitigate effects to water bodies that may occur beyond the 300 metre setback. Mitigation measures proposed include:





- An erosion and sediment control plan will be developed for the site and maintained through the construction and decommissioning phases of the project. This plan will include standard erosion and sediment control measures such as silt fencing, erosion control blankets, hay bales etc.;
- Minimize changes in land contours and maintain natural off-site drainage patterns where possible;
- Develop grading and water flow management plans to emulate pre-construction conditions;
 and,
- Upon completion of project construction, the project location will be vegetated with a mix of native grasses and/or monitored to ensure land naturally re-vegetates within one growing season.

For further detail on mitigation and monitoring plans related to potential effects to natural features and water bodies, please refer to the *Water Assessment* and Appendix D of the *Design and Operations Report*.

6.4 Air, Odour and Dust

Once operational, the renewable energy facility is not anticipated to create dust, odour or emissions to air except as a result of some maintenance activities. During construction, an increase in particulate matter (dust) may be experienced in the adjacent area, which is predominantly agricultural and forested, as a result of construction activities such as clearing and grubbing, grading and levelling, construction of access roads and travel of construction vehicles and equipment over gravel roads. Additionally, there will be emissions from the diesel engines of construction machinery and equipment which may cause temporary negative impacts to local air quality and odour nuisance.

The impacts will be localized and temporary and will not have a significant impact on regional air quality or climate change. Appropriate air quality mitigation measures (such as keeping equipment properly maintained, minimizing vehicle idling and watering roads to reduce dust, as required) will be implemented during construction and should keep these negative impacts to a minimum.

6.5 Noise

During the construction period, which is expected to be 6 - 9 months, construction activities may lead to elevated levels of noise in the area. Mitigation measures will reduce the impact of construction noise on surrounding land uses (e.g. maintaining equipment in good working order,





and prohibiting vehicle idling where possible). Minimal noise (vehicles, spray washing) could also be experienced by nearby receptors during times of periodic maintenance. Efforts will be made to minimize this noise and the project will comply with applicable By-laws and restrictions. Based on the results of the *Noise Study Report*, no noise mitigation measures are required to ensure that noise levels meet MOE requirements. Without mitigation measures, the project complies with the MOE environmental noise guidelines. For more information, please refer to the *Noise Study Report*.

Land Use and Resources

The planned solar facility will occur within lands zoned by the Town of Georgina as 'Rural' and has been under agricultural production of row crops and the solar facility will temporarily alter the land use. Mitigation measures will be undertaken to ensure there are no impacts to surrounding land uses, which are primarily agricultural operations and residential dwellings. The project location could be returned to its pre-construction condition or future anticipated land use after decommissioning.

The proposed facility is physically low-profile and would be non-obtrusive to the surrounding community. Visual impact studies will be conducted as necessary and landscaping will be implemented as required.

6.6 Provincial and Local Infrastructure

Periodic traffic disruptions may occur along Old Homestead Road during the construction phase of the project and damage to roads is possible due to heavy and frequent construction vehicle and equipment travel. Roads will be returned to or maintained at pre-construction conditions. All half-load restrictions as required by local municipalities will be respected by the EPC contractor for the duration of the construction period. GoldLight LP will work with the municipality to address any concerns that may arise during construction with respect to potential road damage.

Connection of the solar facility with Hydro One's existing distribution line may result in some temporary power outages of short duration to local customers. Connection to the provincial grid has been considered under the FIT program and no negative effects are anticipated during the operational phase of the project. Any mitigation measures to minimize power outages will be undertaken by Hydro One.

6.7 Public Health and Safety

Potential impacts to public health and safety are minimal but include those generally related to construction. Noise, vibration, dust and equipment emissions during construction are the key causes of human health impacts. These effects will likely be small, localized and temporary in nature





and mitigation measures will be implemented to address or minimize the impacts. Mitigation measures include: maintaining equipment in good working order; traffic management; prohibiting vehicle and equipment idling, where possible; and watering down of roads as necessary.

Although highly unlikely, there is also limited potential for injury or death related to the operation of construction equipment and vehicles. Temporary and permanent fencing will prevent unauthorized access and ensure public safety during the construction and operational phases. Applicable safety policies and procedures will be adhered to during the construction phase of the project. Construction activities will be conducted by licensed on-site contractors in accordance with Health and Safety Plans and applicable regulations.

In addition, it should be noted that there is limited potential for fires at the project location. The solar PV panels and related equipment represent a negligible increase in fire potential. Risk for vegetative fuel build-up is minimal and will be no greater than when the land was used for agricultural purposes.

Emergency Response and Communications Plans will also be prepared in the event of an emergency on the site and will provide key contact information for relevant responders, regulators, landowners and other stakeholders. These plans are discussed in further detail in the *Design and Operations Report*.

6.8 Areas Protected under Provincial Plans and Policies

The project location is in and adjacent to areas subject to Land Use Plans. Specifically, the project location falls within the Greenbelt Protected Countryside, Greenbelt Natural Heritage System and Lake Simcoe Watershed. The project location does not fall within the Niagara Escarpment or the Oak Ridges Moraine. No impact is expected to areas protected under provincial plans and policies. Additional natural environment studies, as stipulated by *Ontario Regulation 359/09* for project locations within Plan Areas will be conducted and will consider the full intent of the *Greenbelt Act* and the Lake Simcoe Watershed Protection Plan.





7. Benefits of the Project

The generation of power from solar energy will displace approximately 10 MW AC of electricity that otherwise may have been generated by fossil fuel burning or non-renewable power plants. As a result the energy generated will not contribute to climate change or emissions-related health impacts. A further benefit is that local jobs will be created, especially during the construction phase. The project supports the goals of the Province's *Green Energy and Green Economy Act*, 2009.

